Sl. No.	Items of work	Unit	Sanctioned		Rate quoted	
			Quantity	Rates	Figures	Words
				Rs. a. p.		
4	Turfing and watering till it is satisfactory..	S.yd.	7,000	0 0 10		
5	Providing new grade stones with bed slabs cut and painted	No.	6	2 0 0		
6	Removing and refixing old grade stones including figuring, painting and bed slabs	„	15	0 8 0		
7	Figuring and painting Register No. stone..	„	1	0 8 0		
8	Do B. M. stones ..	„	2	0 8 0		
9	Do Gauge stone ..	„	1	5 0 0		
10	Rough stone revetment new with the required lead, lift, jelly backing and jelly wedging, etc.	C.yd.	60	2 0 0		
11	Removing and resetting old stone revetment	„	50	1 0 0		
	II. Waste Weir R.L. 52·00.					
1	Removing burnt stone coping slabs set in mortar	S.ft.	133	0 0 6		
2	Burnt brick in surki mortar	C.ft.	330	0 5 0		
3	Burnt stone jelly concrete in surki mortar	„	380	0 4 6		
4	Cement plastering to concrete apron ..	Sqr.	3·50	8 0 0		
5	Resetting old slabs in surki mortar ..	S.ft.	133	0 2 0		
6	Providing and fixing new burnt stone slabs one line dressed in surki mortar ..	„	20	0 6 0		
7	Plastering with surki mortar	Sqr.	4·00	3 8 0		
8	New rough stone revetment with the required lead, lift, jelly backing and jelly wedging, etc.	C.yd.	13	2 0 0		
9	Earthwork for raising wings of weir including consolidation	„	25	0 3 6		
10	Repairs to old revetment	L. S.	..	6 0 0		
	III. Sluices.					
1	Repairs to sluice (details to be given during execution)	L.S.	..	30 0 0		
	IV. Unforeseen items	„	..	100 0 0		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification dated 23rd October 1938.

The attention of the public is invited to the detailed notification dated 19th October 1938, published on pages 1911-1913, Part VI of the *Mysore Gazette*, dated 27th October 1938, calling for tenders for the "Restoration of Gujjanahalli Byrasandra Tank, Registered No. 360/164 of Duggasandra Hobli, Mulbagal Taluk."

The last date for receiving tenders is 21st November 1938 up to 12 Noon.

R. TIPPAIYA,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 25th October 1938.

It is hereby notified for the information of the public that the last date, *viz.*, 25th October 1938, for receipt of tenders for the Restoration of Konankere Minor Tank, Gubbi Taluk, as notified in page 1824 of Part VI of the *Mysore Gazette*, dated 20th October 1938, has been extended to 10th November 1938.

Notification dated 26th October 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M., on 21st November 1938, for "Opening out a new road from Mattighatta to Handankere in Chiknayakanhalli Taluk." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by Treasury challan for Rs. 380 for having credited earnest money to 17 (*a*) Public Works Deposits and be superscribed "Tender for opening out a new road from Mattighatta to Handankere," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per current schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for opening out a new road from Mattighatta in 5/18th mile of Tiptur-Huliyar Road to Handankere Village in Chiknayakanhalli Taluk.

No.	Description of work	Per	Rate	Quantity
			Rs. a. p.	Rs. a. p.
1	Jungle clearing by roots and destroying ant hills ..	Furlong	2 0 0	32
2	Earthwork excavating check drain and using the same for the road surface and forming	C.yd.	0 3 0	5,133
3	Earthwork forming road surface in average embankment of 1 foot and forming by pit gravel	,,	0 3 6	11,293
4	Earthwork for widening tank bund in 6/2 and 3, 4/4 with recess	L.S.	..	..
5	Constructing causeways with rough stone and burnt stone slabs for wheel track (15 feet width)	R. ft.	4 0 0	320
6	Providing and fixing mile stone including cutting, figuring painting, etc., complete	No.	10 0 0	5
7	Do do furlong stones do ..	,,	3 0 0	28
8	Compensation for lands	L.S.	..	..
9	Providing and fixing finger post	No.	25 0 0	1
10	Road margin to be fixed with stones on both sides ..	L.S.	..	..
11	Consolidating gravel	Furlong	10 0 0	32
12	Planting avenue trees, etc.	L.S.	..	..

Notification dated 26th October 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M., ON 21st November 1938, for opening out a new road from Doddagollahalli to Hebbur in Tumkur District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. to 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury challan for Rs. 380 for having credited as earnest money and be superscribed "Tender for opening out a new road from Doddagollahalli to Hebbur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per current schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for opening out a new road from Chandrasekharapura to Hebbur (Doddagollahalli to Hebbur Section—3½ miles in length).

No.	Description of work	Per	Rate	Quantity
			Rs. a. p.	
1	Jungle clearing roots entirely grubbed up	Mile	5 0 0	3½
2	Cutting and removing prickly piers and trees	,,	6 0 0	3½
3	Removing ant hills and filling with sand	L.S.	..	..
4	Earthwork excavation and using earth for raising the road in ordinary and gravelly soil	C.yd.	0 3 0	8,845
5	Earthwork for embankment	,,	0 4 0	5,837
6	Forming the road surface	S.yd.	0 0 1	18,480
7	Excavating and stacking gravel	C.yd.	0 5 0	1,320
8	Carting gravel (¾ mile lead)	,,	0 3 6	605
8(*a*)	Do (¼ mile lead)	,,	0 2 6	605
9	Spreading gravel	,,	0 0 6	1,320
10	Consolidation of gravel and road	S.yds.	0 0 2½	18,480
11	Collection and spreading sand	C.yd.	0 4 0	112
12	Forming sides	S.yd.	0 0 1	12,320
13	Improving the bund of Gokatte, such as revetment, etc.	L.S.	..	..
14	Causeways	R.ft.	3 5 0	176
15	Irrigation tunnel	L.S.	..	..
16	Providing mile stones, cutting figures, painting and fixing, etc., complete	No.	5 0 0	3
17	Do furlong stones do	,,	2 8 0	25
18	Providing road margin stones, top dressed including fixing	,,	0 8 0	114
19	Providing stone finger post, cutting figures, and painting, etc., complete	,,	75 0 0	1
20	Stone road roller 3'×3' with angle iron frame, etc., complete	,,	125 0 0	1

P. RAJAGOPALAN,
Executive Engineer.